

## JT60-SA - WPSA GM Thomson scattering status 04-05-2022

Federico D'Isa

for the EU-TS team





This work has been carried out within the framework of the EUROfusion Consortium and has received funding from the Euratom research and training programme 2014-2018 under grant agreement No 633053. The views and opinions expressed herein do not necessarily reflect those of the European Commission.

# **Performance requirements**



**The core TS system (P2)** shall measure  $T_e$  and  $n_e$  profiles


- **46 positions** from R=2.6m to R=3.725m,
- scattering volume length 15 mm ,
- radial spatial resolution (points distance) 25 mm
- dynamic range 0.1-30 keV
- Laser pulse repetition rate will be **50 Hz**.

**The edge TS system (P1)** shall measure  $T_e$  and  $n_e$  profiles

- 49 positions from R=3.7m to R=4.17m,
- scattering volume length **5.5 mm**,
- radial spatial resolution (points distance)
  25 mm at R<3.9 m, 5 mm at R>3.99 and 10 mm in between
- dynamic range **0.01-10 keV**.
- Laser pulse repetition rate will be **100 Hz**.

For both systems:

The accuracy is expected to be better than 10% for  $T_e$  and 5% for  $n_e$ , at  $n_e = 10^{19} \text{m}^{-3}$  (from simulation)  $\rightarrow Best Effort$ 



#### F.A. D'Isa | WPSA GM | 04 May 2022 3

# **TS diagnostics layout in JT60-SA**

## EU components


## **Core TS** components:

- Optical fiber
- Polychromators

## Edge TS components:

- Optical fiber
- Polychromators
- LASER
- Collection optics







## Laser system: status




# **Î** LOS

The Main Technical Characteristics of the Laser												
Wavelength	1064.2 nm											
Repetition rate	100 Hz											
Energy	> 3 Joules											
Pulse duration	8-18 ns											
Divergence	0.5 mrad											
Beam diameter	ø15 mm, flat top profile											
Pointing stability	< 100 microrad											



- Design documentation ready
- Assembly ongoing
- Payments suspended until June
- Contract still valid
- If there are export issues f4e may procure a commercial laser.




#### F.A. D'Isa | WPSA GM | 04 May 2022 4


# P1 collection optics: status





## **Status of procurement**





- Mechanical parts procured and available in Officina Stellare (OS);
- L1 procured and available in OS
- L2 delivered at the end of April
- L3 procured and available in OS
- L4 procured and available in OS
- Polarizers procured and available in OS
- M1 and M2 (Dichroic mirrors) procured:
  - M1 ready at the end of August
  - M2 available in OS
- Windows: delivery expected by mid May. Coating by end of August.
- Preliminary tests: first and second week of June

# P1 mechanical structure: status


- Collection optics on a retractable arm
- Decoupled from cryostat
- On supporting structure standing on floor
- Same structure to install port plug

Status of procurement

- Support structure and installation procedure informally accepted
- Port plug drawings informally accepted

## Production

- Support Structure & Trolley (contract signed July 2021): manufacturing in progress.
- Port plug assigned to Forth engineering (Contract signed April 2022). Components available and ready to order.



## **Optical Fibers: status - completed**

- Fiber delivery to QST completed
- Fiber bundles under manufacturing by QST





Figure 1: Radiation-induced attenuation in a 200-m fiber irradiated over 10 m, for various doses in kGy.



- Silica core / fluorine silica cladding
  / polyimide coating (max T=150°C)
- 200/220/250 micron
- 0.22 NA

**FBP** 

0.2

0.4

0.9

2.4

kGy

0.1

1

10

100

- 1100 km → 1200 km
- Neutron dose: 0.13 MGy (10<sup>16</sup> n/cm<sup>2</sup>)


F.A. D'Isa | WPSA GM | 04 May 2022 7

# **Polychromators: status**










- Preliminary test successfully passed in November 2021
- mechanical elements: procured and delivered
- Lens/Filter/Mirror procured and available in GNR
- Assembly and alignment: 16 Box ready, works completed at end of May
- APD: procured and available at GNR
- Electronic circuit elements: all purchased and available at supplier.
- Electronic boards: 50 assembled. Others in production.


## **Polychromators test: detector characteristics**





Inspection & acceptance tests 22-23 November 2021

## **Polychromators test**




Inspection & acceptance tests 22-23 November 2021

F.A. D'Isa | WPSA GM | 04 May 2022 10

# **Edge TS performance prediction**

Simulation including:

- Polychromator experimental transmission
- Fiber experimental transmission
- Optics experimental transmission



Expected performance met

# Status procurement: summary



• Annex B for PA: Approved in Feb 2021 (https://users.jt60sa.org/?uid=2A77BS)

#### • Fibers

F4E procurement contract with Polymicro-Molex closed in October 2021. Fiber delivered to QST. Successfully concluded. Fiber bundles under production by QST.

#### Polychromators

F4E procurement contract with GNR (Italy) ongoing (KOM 03-11-2020): Design passed test in November 2021 (uid=2CYP9J)), All components are procured. 16 Polychromator are assembled.

#### • Optics edge TS (P1)

Procurement contract with Officina Stellare (Italy) ongoing (KOM 24-11-2020): design approved in April 2021 (uid=2A5UVQ), assembly in progress (issues with M1 and L2), test to start first week of June.

#### • Laser edge TS (P1)

Procurement contract with LOS (Russia) ongoing: design report approved in January 2022 (uid = 2D3BJH), components purchase ongoing, payments suspended until June. Risk to stop the contract losing Eurofusion budget: plan B-purchase in 2023 by F4E.

#### • Mechanics edge TS (P1)

Pending drawings and installation procedure informally approved; Manufacturing MKT (Romania) of support structure ongoing; Contract for port plug with forth engineering signed April 2022. Raw materials being purchased.

## PLANNING



				201	9			Τ					2021								2022								_		20	)23	;		Γ	2024										
	Q1		Q2	2	Q3		Q4		Q1		Q2		Q3		Q4		Q1		Q2		Q3		Q4		Q1		Q2		Q3	C	<b>Q</b> 4	C	<b>)</b> 1	G	22	(	23	(	<b>Q</b> 4	(	ຊ1	Q	2	Q	3	Q4
	1 2	3	4 5	6	7 8	9 1	0 11	12	1 2	3 4	5	6 7	8	9 10	11	12	1 2	3 4	5	6 7	8	9 10	) 11 ·	12 1	2	3 4	5	6 7	8 9	9 10 1	11 12	1	2 3	4	5 6	6 7	8	9 10	11 12	2 1	2 3	4 5	6	7 8	9 10	0 11 12
																																								2						
Annex B approval																																														
												1	П																																	
Fibers (RFX-IFAC)										ΤI	KOI	Μ																																		
Design										T		,																																		I
F4E tender																																														I
Procurement																																								•						I
Delivery																																														
Collection optics (RFX-IFAC)													<b>_</b> '	кс	1																															
Design													Γ.		1	Г																														
Tender															T																															
Procurement																																														1
Delivery to IAP																DR								Р	PC	<b>w</b>	G																			I
Mechanics (IAP)															<b>FL</b>	<u>лк</u>								a	ppr	ova	al																			I
Design																Z								_	i./I		1													Ľ	inst	alla	itio	n		
Drawigs production																														↓											in	То	rus			
Procurement																																										Hal				
Optics integration & test																																							<u> </u>				<u> </u>	1		
Delivery & installation																																					sto	rage	e _							1
Polychromators (RFX-IFAC)													Γĸ	O	И.								1	t n		chr	 	atoi	Ĺ							at	QS	Т	_							1
Design & R&D																									ptai																					I
F4E tender																							J	I		1			ιT																	
Procurement																							ΤŤ																							
Delivery & installation																Т			П																											
P1 Laser (RFX)																							Fi	nal	des	ign	Ī				1												11	1		1 il
Tech spec & input optics design																							Ī				, t				Ехро					$\square$							T	ve	sse	ı İ
Procurement																T							Ú							₩ F	Ruse	siai	ssu	iesi	? -	$\square$							F	clo	sec	١ţ
Delivery & installation									$\square$				$\square$		П																	Π				$\uparrow \uparrow$				$\square$			Τı			
Align, calib & commissioning													ТŤ				T																													




# Thank you for the attention

F.A. D'Isa | WPSA GM | 04 May 2022 <sup>14</sup>

# **TS diagnostics layout in JT60-SA**







# **P1 collection optics**










#### **Final Design review: February 2021**

## **P1 collection optics**






## **Polychromators test**



## **Detector gain stabilization**



Inspection & acceptance tets 22-23 November 2021

F.A. D'Isa | WPSA GM | 04 May 2022 <sup>18</sup>

# **Polychromators assebly**

## **16 Polychromator Box assembled**

Polychromator operational P1.01,P1.04 and P2.01






#### Inspection & acceptance tests 22-23 November 2021

## Nd:YAG laser system for JT-60SA TS diagnostic




Experimental prototyping of Master Oscillator and Amplifier

Near field of the Laser (*E*=3J, 100Hz)



Far field of the Laser (E=3J, 100Hz)




Spot in the far field < 2×DL


Experimental prototyping has shown that the characteristics of the laser system will meet the Technical Specifications

Contacts: Aleksei Kornev afkornev@hotmail.com

#### Master Oscillator Pulse



#### Pulse Shape at Output Energy E=3J



#### F.A. D'Isa | WPSA GM | 04 May 2022 20

## P1 mechanical structure



### Support structure manufacturing started

