

JT-60SA Massive Gas Injection system Status and project plan

M. Dibon, G. Matsunaga, S. Nakamura, G. Phillips, C. Sozzi Acknowledgement: G. Giruzzi, M. Hanada





This work has been carried out within the framework of the EUROfusion Consortium and has received funding from the Euratom research and training programme 2014-2018 under grant agreement No 633053. The views and opinions expressed herein do not necessarily reflect those of the European Commission.

System capabilities



Key properties

	Valve Type 5
Gas reservoir per valve [cm³]	815
Max. gas pressure [MPa]	6.5
Max. gas amount [Pam³]	5300
Max. inj. Particles	1.28*10 ²⁴
Gas injection time [ms]	~ 10
Injection timing accuracy [ms]	< 1
Gas mixing capability	Up to 4 different gases
Mixing accuracy [bar]	0.2
Valve positions	Upper oblique LFS Se9 + Se18
Expected average distance to separatrix [mm]	~ 100
Temperature of injected material [°C]	~ 50

Current status






Trigger electronics

Profibus cable (110 m)
Central PLC <-> gss panel

Central PLC

Control PC



Vacuum Feed throughs

Gas panel

Atmospheric trigger and signal cables (250 m) and (280 m)

Current status



MGI valves in manufacturing




Bellows ordered, will hopefully be delivered soon Offer for in-vessel cables received, not yet ordered H2 pressure booster is ready to be ordered

Current status



Control program



Future activities



- Valve testing at IPP
 - Function tests
 - Pressure test at 100 bar (1.25 times design pressure)
 - Vacuum leak test in hot and cold states
 - Inspector from QST on site
- System testing at IPP
 - Full setup of MGI system in the lab
 - Test of manual and automatic operation modes
 - Documentation
- Packing and shipping
 - Transfer of ownership from IPP to F4E
 - F4E organizes packing and transport
- System inspection on arrival in Naka
 - Unpacking and on-site inspection
 - Quick assembly of the system for function test of possible
 - Transfer of ownership from F4E to QST
- Installation of the MGI system in Feb 2024

Project plan



	M 22	J 22	J 22	A 22	S 22	O 22	N 22	D 22	J 23	F 23
MGI valve manufacturing										
In-vessel cables manufacturing										
MGI valves function tests										
Pressure / leak tests										
System tests										
Packing and shipping										
On-site system inspection										