



**FUSION
FOR
ENERGY**


JT-60SA Actively Cooled Divertor

Design, procurement and qualification activities


V. Tomarchio
Fusion for Energy



The JT-60SA Actively cooled divertor




- 36 nearly identical units
- Actively cooled (steady state operation)
- 10MW/m² nominal steady state heat load (targets)
- Graphite armor
- CuCrZr/TZM heat sinks




- Procurement split in 4 contracts:
 - **High heat flux elements**
 - **Normal heat flux elements**
 - **Cassette frames**
 - **Diagnostics and integration**




The High Heat Flux Elements




- Design features:
 - Isotropic graphite armor (SGL Carbon Sigrafine R6710)
 - TZM heat sink
 - Internal nickel coating
 - Stainless steel swirl tape
 - Diffusion bonded tiles
 - Laser welded 316L pipes
 - 10 MW/m² steady state nominal heat flux
 - 15–20 MW/m² short pulses




- Requirements:
 - Operating pressure 20 bar
 - Joint temperature 900 C (up to 1400 C on short transients)
 - Leak rate $< 10e^{-8}$ Pam³/s
 - 13000 nominal power cycles
 - Inlet water temperature 40 C
 - Mass flow rate 0.8 kg/s



- Scope of contract:
 - 12 small + 12 full scale mockups
 - 1020 standard elements
 - 30 custom element for Langmuir probes



- Qualification activities:
 - Diffusion bonding trials – small square samples
 - Welding trials – pipe samples
 - Material tests – graphite and TZM
 - Mechanical
 - Thermal
- Mechanical tests
 - Diffusion bonding destructive test
 - Laser welding destructive test




The High Heat Flux Elements



Small diffusion bonding sample




Destructive testing => 120 Nm




Bonding iterations



8 x small scale mockups




Infrared Thermography tests



Infrared Thermography tests

The High Heat Flux Elements



Laser welding trial



Ni Coating samples




Hot leak test at 200 C 25 bar




Corresponding leak rate

The High Heat Flux Elements




Diffusion bonding sample with defects




Completed, waiting for tests (UT, IR thermography, HHF)

The High Heat Flux Elements





Full scale mockups – pre-series




Destructive tests


The Normal Heat Flux Elements




- Design features:
 - Isotropic graphite bolted tiles
 - CuCrZr/SS316L heat sink
 - Graphite sheet compliant layer
 - 2 MW/m² steady state nominal heat flux
 - 10 MW/m² short pulses




- Requirements:
 - Operating pressure 20 bar
 - Leak rate $< 10e-8$ Pam³/s
 - 13000 nominal power cycles
 - Inlet water temperature 40 C





- Scope of contract:
 - 36 NHF element sets + 2 spares
 - Graphite tiles
 - Heat sinks
 - Chevron units
 - Manifolds
 - Branch pipes
 - Graphite sheets
 - Fasteners




The Normal Heat Flux Elements




T=3700 s




Full 3D thermal analysis




- Design features:
 - SS316L frame and pipes
 - Standard frame construction
 - Customized pipes (left, right)
 - Compatible with LBW on site




- Requirements:
 - Operating pressure 20 bar
 - Leak rate $< 10e^{-8}$ Pam³/s
 - Inlet water temperature 40 C





- Scope of contract:
 - 36 cassette frames + pipes + 2 spares
 - Bellows
 - Tee junctions






Full 3D structural analysis



ODB: J_JT60DIV_062_EM.odb Abaqus/Standard DBEXP/SEQUENCE R2017x Mon Feb 20 18:46:14
Step: EM
Increment 1: Step Time = 1.000
Primary Var: S, Mises


Thermal + pressure + EM loads (disruption)





Supplier 3D models – now in preparation for material purchase

- The 36 units will be integrated in a facility in Europe
- The call for tender is being prepared and should be launched this year
- The diagnostics for the ACD include:
 - Langmuir probes
 - Thermocouples
 - Halo current coils
 - Diagnostic openings







Langmuir probes design




Tantalum






Langmuir probes thermal analyses

- Integration activities include:
 - Precise positioning of the PFC on the cassette frame
 - Mechanical connection of the components
 - Installation of diagnostics
 - Welding of all pipes + NDE
 - Pressure and (hot) leak testing
 - Flow test



HHF alignment during integration





Diagnostics and integration

