

4<sup>th</sup> meeting for CN-EU DEMO cooperation, KIT, March 19-22, 2024, Germany

# Overview of Comprehensive Research Facility for Fusion Technology (CRAFT)

Jiangang LI for CRAFT team




# Chinese Fusion Engineering Test Reactor



$R=7.2\text{m}$ ,  $a=2.2\text{m}$ ,  $B_t=6.5\text{T}$ ,  $P_f=1\text{-}2\text{GW}$ ,  $TBR > 1$ ,  $65000\text{t}$

## Full cycle of fusion power plant

- Fusion power  $> 1500$  MW
- Duty time  $\sim 50\%$
- Burning plasma with  $Q \geq 10\sim 30$
- Tritium self-sustaining ( $TBR \geq 1$ )
- Material and components validation
- Electricity generation



**Physics design by V.Chan. It will be CN-DEMO. Can we build it successfully?**



# Objective of CRAFT

- Explore and master fusion DEMO level key technologies
- Establish the method and standard for manufacture the key material, components and system for CFETR.
- Building key prototype systems for CFETR
- Testing and validating the method, technology and system for a successful construction of CFETR
- Building RAMI for key CFETR systems
- Training next generation of fusion scientist , engineer and mangers.





# Lists of systems & facilities of CRAFT

• 1. SC Material testing facility	• 11. <b>CFETR divertor development</b>
• 2. SC Conductor testing facility	• 12. CFETR divertor testing facility
• 3. TF magnets testing facility	• 13. <b>Blankets developments</b>
• 4. CFETR CSMC and testing facility	• 14. <b>ECRH System</b>
• 5. <b>CFETR HTS coil and testing</b>	• 15. <b>NNBI system</b>
• 6. <b>CFETR TF and testing</b>	• 16. <b>LHCD system</b>
• 7. Cryogenic testing facility	• 17. <b>ICRF system</b>
• 8. Power supply testing facility	• 18. Blanket testing facility
• 9. Large Linear plasma testing facility	• 19. RH & testing facility
• 10. Mater Control facility	• 20. VV and installing testing facility

Auxiliary system	1、 Power distribution system	3、 Campus
	2、 Cooling water system	4、 Buildings

# 1. SC Material testing facility






## ➤ Scientific objectives

- To master scientific and the intrinsic physical properties and service behavior of materials for superconducting magnets in complex and extreme environments, and to carry out engineering application research.

## ➤ Composition and main parameters

- SC material performance research platform: 19 T, 2 kA
- AC Loss research platform: 0.01-0.2 Hz, 1500 kN/m
- Structure material performance research platform: 2500 kN
- Thermo-hydraulic research platform: 3.8-300 K
- NDE technology research platform: 350 kV (X-Ray)
- High voltage research platform: 0-100 kV

Will be finished on Nov.2024






# 2. SC Superconductor Testing Facility

## ➤ Scientific Objective

- To study the electro-magnetic behaviors ( $T_{cs}$ ,  $I_c$ , AC loss, MQE) of composite structure superconducting conductor under mult-field coupling condition;
- To evaluate the reliability of SC conductor in future fusion reactor operation condition;

## ➤ Main Technique Parameters

- Maximum magnetic field: **16.5 T** ( $B_{back}=15\text{ T}$ )
- Tested space: **100 × 160 × 550 mm**
- Field homogeneity: **≥ 98 %** (tested space)
- Maximum tested current: **100 kA**



## 2. SC Superconductor Testing Facility

### □ 15 T DC magnet – **Dummy Model Coil Wind**

- HF&MF layer coil winding line



Length: 22 m, Width: 8 m, Working height: 1.8 m

- LF pancake coil winding line






Length 32 m, Width 10 m, Working height: 1.8 m

- Manufacture and commissioning of **two coil winding lines** for 15 T DC magnet **have been completed**;
- **The two dummy model coils** (MF model coil and LF QP pancake coil ) **have been wound**, the geometric dimensions are in line with the expected values; **one year delay**



# 3. TF magnets testing facility

To perform the large-scale SC magnet research on mechanics, thermology and electromagnetics properties. To evaluate the SC magnet system compatibility, reliability, stability, and magnet safety in fault state and verify the reliability of magnet engineering technology.




- Quench detection system
- Protection system
- Cryogenic system
- Fast discharge
- Vacuum system


Item	Description
Cryostat main dimension	<b>Length&gt;28.5m ; Width&gt;14m ; Height&gt;6m</b>
Operation temperature	4.5K
Current leads operation current	100kA/60kA
SHe pressure	3-6 Bar
SHe massflow	>500 g/s

**Large-scale Magnet Performance Research**

### 3. TF magnets testing facility



1. TF magnets testing facility is about **one year delay**
2. Start fully test on July
3. Start test 1<sup>st</sup> TF pancake on Nov.
4. Start test BEST TF (3 each time) from next Feb



# 4. CFETR CSMC and testing facility





## Objective:

Develop magnet technology of CFETR Nb<sub>3</sub>Sn CS

Carry out experiments on electromagnetism, magnetism, thermodynamics performance of magnets under fast magnetic field environment

Evaluate the safe operation characteristics of magnets

### Quench detection



$\Phi_{in}$	1500mm
$I_{op}$	47 kA
$dB_{max}/dt$	5 T/s
$R_j$	< 1 n $\Omega$
$T_{OP}$	4.5K

## □ Major progress

- ✓ The Dewar and vacuum system has been manufactured and transported to the No.8 factory;
- ✓ On-site installation and off-line high voltage and high current commission of power supplies will be finished in Aug.;
- ✓ The installation of Cryogenic system will be finished in July and commission will begin.
- ✓ The assembly of five coils is expected to be completed by the end of September.



Will be finished in the end of April


# 5. HTS magnet technology development

## The objectives

- Explore HTS CICC conductor and magnet technologies
- Evaluate operation reliability for the next fusion device


	Parameters	Values
Coil	Operation current / $I_{op}$	46.5 kA
	Peak field / $B_{max}$	19.6 T
	Inner radius	475.5 mm
	Outer radius	703.5 mm
	Number of turns / per module	5 x 30 turns
	Conductor length per module	556 m
CICC	Cable OD	32 mm
	Jacket OD	~ 41 mm
	REBCO Tape(width x thickness)	4 x 0.1 mm
	No. of sub-cable	6
	No. of SC tapes	212

## Preliminary design concepts




Candidate material: REBCO tape




Option I:



Option II:



CICC design under developing







# HTS magnet technology development



## Sub-cable:

- Develop automatic cabling machine
- Sample performance →  $I_c=10.6\text{kA}@20\text{T}, 4.2\text{K}$
- Long cable manufacturing →  $L=110.6\text{m}$



## Full size conductor:

- Two sample legs were prepared → **2.7m per leg**
- Sample performance → **47kA@10.8T, 4.2K, stable**
- New optimized samples expected to finish in October



**Final CICC conductor test will be April, Sultan**

# High strength Structural Material for CS&TF

- Modified N50 was developed for magnet of future fusion reactor.
- China has the mass production capacity of jackets, forgings and welding material.
- The production of jackets with a total length of 2000 m and 2 full-size forgings has been completed.







Fig 1. Mechanical property of jacket @ 4.2 K

First HTc CS coil will be finished and tested in the end of 2025

# 6. CFETR TF and testing

## ➤ Objective:


- To construct a **prototype TF coil** meeting the physical and engineering requirements of CFETR
- To develop and validate of fusion reactor **large-scale superconducting coil** manufacturing technologies and standards

## ➤ Main Technique Parameters:

Items	Value
$I_{op}$	95.6 kA
$B_{max}$	~14.5 T
Total Storage Energy of 16 TF coils	~120 GJ
Total Inductance of 16 TF coils	26.3 H
$T_{op}$	4.5 K
Insulation Voltage	>10 kV
Height × Width	21.7 × 12.3 m
Total weight	~743 t


## ➤ System Description:

### ✓ Preliminary design model




WP, coil case, coil support

### ✓ CFETR magnet system




- CS coil × 8
- TF coil × 16
- PF coil × 7
- 3 grades conductors** has been adopted





## Coil Internal Joint (216) Technology



SULTAN sample




Figure 13: Resistance (nΩ) vs number of performed EM cycle for the left leg at 4 T and 85 kA. The points recorded at 2 T, 6 T/50 kA and 8 T/50 kA are also shown.




Figure 14: Resistance (nΩ) vs number of performed EM cycle for the right leg at 4 T and 85 kA. The points recorded at 2 T, 6 T/50 kA and 8 T/50 kA are also shown.

- ✓ after 1000 excitation cycles and 2 WUCD, **joint resistance < 0.3nΩ @ 4T x 85kA**, and the resistance changes little.
- ✓ after 1000 excitation cycles, joint resistance **< 0.3nΩ @ 8T x 50kA**.


The technology is **firstly developed** for hybrid graded winding coil **in the world**, performance is **excellent!**

## Coil Case Design and Manufacturing

- High Strength high-Mn austenitic stainless steel (**JJ1 Forging Material**) development



Forging 1-10T ESR ingot



Forging 2-30T ESR ingot

- ✓ yield strength @ 4.2K > 1000MPa
- ✓ fracture toughness @ 4.2K > 200 MPa·m<sup>1/2</sup>

**New material in China which is +20% on yield strength @ 4.2K than ITER-316LN!**


- QA/QC
- High performance SC wirl ( Sultan)
- Long length cable
- CICC conductor (sultan)
- Long length CICC conductor (950m)
- Isolation material

## Winding Pack Design and Fabrication

- Winding line and critical equipment



Winding line  
(commissioned in Oct,2022)



heat treatment furnace  
(Under Commissioning)




turn insulation wrapping system  
(Under Commissioning)

- Internal joint fabrication



Procedure and tooling are qualified.

- Dummy coil winding




Procedure and tooling are qualified.  
**Dimension within tolerance.**

# CRAFT TF Coil Progress



**4 / 9 coils have been made**




**Heat treatments will start next month**

**TF coil will be fully tested in Sep. 2025 ( 5 month delay)**

# 7. Cryogenic testing facility

**Objectives:** To provide the cryogenic testing facility for CRAFT SC system.

To build a research and test platform aiming the technology development of future CFETR cryogenic system.



Will be finished on end of 2024

# 8. Power supply testing facility

## ➤ Objective

- ❑ To solve the key issues of current tokamak coil power supply ;
- ❑ To develop the advanced (next generation) tokamak coil power supply ;
- ❑ To support the research and test of large current super-conductive magnet systems .

## ➤ Parameters


### Feeding Coils:

Current Source Converter: 100 kA, 250 V  
 Voltage Source Converter: 60 kA, 3000 V



### In case of quench :

Dissipated Power: 1GJ  
 Breaking time: <0.5 s


Current Source Converter




Voltage Source Converter



Quench Protection System



Statcom



## New World Record Achieved

- **100 kA** DC vacuum circuit breaker for quench protection system
- **100 kA** pyrobreaker for quench protection system
- **2.1m\* 2.1m \*2.1m** large scale SMF (Static Magnetic Facility) put into use



## New Technology Adopt

- Low frequency -harmonic reactive power integrated compensation, **prototype applied to industry**
- Energy storage power compensation technology, **prototype applied in coal power industry**
- 15 kA Voltage source converter applied in **EAST.**



**Project goes well, commissioning started.**

# 9. Large linear plasma testing facility

**Objectives:** To address key R&D issues of plasma-facing materials and components for CFETR in appropriate physical regimes, size and time scales of plasma-material interactions.


## Capabilities

Delivering DEMO divertor-relevant plasma streams of high heat and particle fluxes for material/mockup testing

In-situ/in-vacuo analysis for material surfaces

## Machine parameters

Shot length	~1000 s - hours
Magnetic field	~3 T
Particle flux	$10^{24} - 10^{25} \text{ m}^{-2}\text{s}^{-1}$
Plasma dimension	30-100 mm
Max. Sample/mock-up size	250×250 mm




# Large linear plasma facility


## □ Progress

- Machine design is finalized and key components (e.g. SC magnet) are under manufacturing.
- A pilot machine (1T ) has been built to develop plasma source technology.
- $\sim 10^{24} \text{ m}^{-2}\text{s}^{-1}$ ,  $>24 \text{ h}$  steady-state plasma discharge has been achieved.


Pilot machine



Typical discharges



$>10^{24} \text{ m}^{-2}\text{s}^{-1}$  flux for  $>24 \text{ hours}$



Will be finished on end of 2024




# Large linear plasma device

## □ Recent progress of the large linear plasma device

- The 3 T SC magnet has been fabricated successfully and is under cryogenic test.
- Manufacturing of vacuum chambers and supporting structure will be finished at the end of March, 2024.
- A prototype machine with  $\sim 10^{24} \text{ m}^{-2}\text{s}^{-1}$  particle flux is open to users for PWI experiments for one year.


The 3 T SC magnet  
under testing



Vacuum chambers and  
supporting structure




The prototype machine  
for PWI experiments




# 10. Mater Control facility

➤ Scientific objectives : providing IT support for CRAFT campus and establishing numerical tokamak for CFETR plasma control system and discharge scenarios assessment.



## Campus IT support (in use)

- Network communication
- Data storage and service
- Timing and synchronization
- Interlock and monitoring



## Numerical Tokamak (XIAO, YUAN on 20th)

- Control simulation
- Design and verification of discharge scenarios
- Event analysis and handling
- Discharge assessment
- Diagnostic technical development

## □ Construction objectives:


By optimizing preliminary design and implementing R&D of small, medium-sized test mock-ups and prototype fabrication, it will determine the final engineering design of CFETR divertor.

## □ Main technical parameters

- Heat load capacity in strike point area sustaining steady state heat flux of  $20 \text{ MW/m}^2$
- Profile error of plasma facing surfaces (PFCs) is less than 1 mm


## □ Key technologies progress:

### ● Material connection technology for fusion reactor materials



Two material connection routes

Route 1



Route 2


**Medium-sized test mock-ups of two routes:**

**UT:** no defects exceeds  $\Phi 2 \text{ mm}$  equivalent.

**Profile error of PFCs:** less than 1 mm.

**7 MPa pressure test:** meets required He leakage rate of  $1 \times 10^{-10} \text{ Pa} \cdot \text{m}^3/\text{s}$ .


## ● Hybrid divertor-blanket integration



Blanket (conceptual design) and divertor (engineering design)

Blanket design	I (Without any windows)	II (I + Considering all auxiliary systems)	III (II+Hybrid divertor-blanket)
TBR	1.147	1.029	1.175

## ● Independent RH dismantling technology for targets




Engineering design of divertor

**The divertor is ready for prototype fabrication:**

- All targets could RH from plasma side in design
- Preliminary feasibility analysis meets the requirements



## ● High heat load (20MW/m<sup>2</sup>, SS) handling technologies



Small sized mock-up



Route 1



Route 2

**20 MW/m<sup>2</sup>, 1000 cycle (15s on, 15s off), HHF testing passed**

# 12. CFETR divertor testing facility

**Objectives:** Provide testing environment of high thermal radiation loads and thermal hydraulic performance for water-cooled and helium-cooled divertor and blanket. The integrated testing for prototypes divertor to verify its performances.

## ➤ Key parameter

### Steady state heat flux with EBG: 20MW/m<sup>2</sup>

Parameter	EBG-I	EBG-II
Max. power	800 kW	60 kW
Max. accelerating voltage	60 kV	120 kV
Pulse length	0.2s~∞	1ms~∞
Deflection angle	±15deg	±15deg
Deflecting direction	xy	xy
Deflection frequency	10kHz*deg	10kHz*deg
Min. beam spot Diameter	5mm(60kV)	1mm(120kV)

### Water coolant loop


Operation pressure	Coolant temp.	Max. mass flow rate
15.5 MPa	285-325 °C	120 m <sup>3</sup> /h

### Helium coolant loop

Operation pressure	Coolant temp.	Max. mass flow rate
8 MPa	300-500 °C	3 kg/s

### Vacuum chamber

Diameter	Length	Pressure limit
3 m	4 m	1 MPa





**Started in operation from 2023**



# EAST Lower divertor Validation

## Technical specification & parameters

	Mono-block type	Flat plate type	Notes
Quantity of Modules	42	6	Total: 48
Heat flux capability	10MW/m <sup>2</sup>	20MW/m <sup>2</sup>	Steady state
Cooling water	Max flow velocity: 8m/s, Inlet: 20°C		Total: 650 ton/h
Work pressure	3MPa, Test: 3.8MPa		







**Mono-block type**  
 ITER-Like design  
 Steady state: 10MW/m<sup>2</sup>




**Flat plate type**  
 Hyper-vapotron design  
 Steady state: 20MW/m<sup>2</sup>

Based on the parameterized design method, the optimal fin geometry size was obtained with the goal of reducing the maximum temperature.



# 400s H-mode in EAST

## ✓ Demonstration of Reliable 403 Seconds Stationary High Confinement Plasmas




- A full non-inductive with  $n_e/n_{GW} \sim 0.7$  and  $f_{BS} > 50\%$  by RF heating with zero torque injection
- $H_{98,y2} \sim 1.35$  /  $T_e > 8.5\text{keV}$  with ITB by electron dominant heating
- Key issues on particle balance and heat load with actively cooling W-divertor ( $R \sim 0.92$  and  $T_{Surf@Div} < 600^{\circ}C$ )
- Small ELMs throughout the discharge, with high core performance ( $\beta_P \sim 2.5$  /  $\beta_N \sim 1.5$ )
- Heat loads on new divertor is about 8.7 MW/m<sup>2</sup>.

# 13.blanket : Water cooled ceramic breeder



## Design strategy

### Hydraulic decoupled concept for blanket heat removal


- Two independent cooling systems (CSs): CS1 for FW and CS2 for BZs.
- Easy to adjust mass flow for CS1 and CS2 independently during multiple power operation (0.2/0.5/1/1.5GW)



## Structure features for normal blanket modules



### Neutron flux distribution



- Stiffening plates (SPs) divide the steel blanket box into several sub-zones to enhance the structure.
- The FW is a U-shaped plate bended in the radial-toroidal direction and cooled by water.
- Cooling tube assemblies (CTAs) are embedded in BZs filled with mixed pebble beds for heat removal.
- The ribs are bonded with SW/SP to enhance the blanket box structure.

**Global TBR is 1.17, 33% efficiency**


## Material selection

	material	parameters
<b>Coolant</b>	Pressurized water	15.5 MPa, 285°C/325°C
<b>Structure</b>	RAFM/ODS steel	Allowable temp. ≤550/650 °C
<b>FW armor</b>	Tungsten	Allowable temp. ≤1300 °C
<b>Breeder and multiplier</b>	Li <sub>2</sub> TiO <sub>3</sub> & Be <sub>12</sub> Ti mixed bed	Allowable temp. ≤900 °C and >400°C (tritium release)
<b>Purge gas</b>	He+0.1%H <sub>2</sub>	0.1-0.3MPa, 0.1-10 cm/s

## R&D activities


### Fabrication technology

#### HIP+EBW technology




#### 3D printing technology

- High temperature mechanical properties of SLM-ODS-RAFM are significantly improved.
- The additive manufacturing work of U type WCCB module was completed.



### Neutronics experiment



- TPR measurement by online lithium glass detector and offline liquid scintillator
- Calculated/Experimental results of TPR are consistent





# Supercritical CO<sub>2</sub> cooled Lithium-lead (COOL) blanket

## Design strategy


- ❑ **Coolant conditions:** (1) S-CO<sub>2</sub> for structures: 8 MPa, ~350/400 °C over DBTT for RAFM; (2) PbLi for BZs: ~0.01-0.1m/s, 460 °C /600-700 °C.
- ❑ **Temperature limits:** within material allowable temperature range (@1.5 GW, 0.5MW/m<sup>2</sup> on FWs)
- ❑ **Low MHD effect and weak corrosion:** (1) PbLi-RAFM interface: < 480 °C for avoiding strong corrosion; (2) SiC FCIs: thermal and electric insulating to decrease RAFM temp. and reduce MHD effect.
- ❑ **High thermal efficiency:** (1) outlet temp. of PbLi: 600-700°C; (2) efficient PCS: S-CO<sub>2</sub> recompressing Brayton cycle.

## Advantage

- ❑ **High thermal efficiency:** high PbLi outlet temp. and more suitable for efficient power conversion
- ❑ **Acceptable construction cost:** (1) cheaper neutron multiplier of Pb; (2) abundant CO<sub>2</sub> in natural world
- ❑ **Controllable MHD effect and metal corrosion:** using electrical and thermal insulating Flow Channel Inserts (FCIs)
- ❑ **Enhanced heat removal capacity of S-CO<sub>2</sub>:** larger density than helium (over 10 times @8MPa, 400°C)

## Structure features

Global TBR is 1.18, 45% efficiency




- Single-Module Segment
- U shaped FW coated with Tungsten armor, containing 127 channels, cross section of 12mm\*12mm
- S-CO<sub>2</sub> manifold configured in the back
- SPs and CPs divide breeding unit into several PbLi breeder zones
- PbLi flows through parallel channels from segment bottom to top
- FCIs to mitigate the MHD effect and corrosion
- 5mm gap between FCI and steel wall


CHEN's Talk on 21th

## R&D activities

### Corrosion compatibility of liquid metals



### Neutronics experiment for COOL mockup (out-of-pile)





# 14. ECRH facility

- **Aims:** to address the technical issues as well as to pursue technical solutions for critical components of the future advanced CFETR ECRH system.
- R&D efforts focus on the design and performances assessment of key components, (conditioning of gyrotrons, trans and launcher.
- ◆ **Development and installation of high power CW gyrotron testbench**

Specifications		
1	Frequency	170 GHz
2	Output power	2 MW
3	Pulse length	>60 s



**170GHz**  
**0.4s, 0.56MW**



Test performance validated – 700kW, 3000s pulse duration

**Will be finished in the July of 2025**

# 14. ECRH facility

## ◆ Mockup design of multi-convergency launcher is ongoing

- The multi-beams injection equatorial launcher is designed based on the front steering (FS) concept
- The beam convergence characteristic has been determined by quasi-optical optimization
- Preliminary analysis of thermal-mechanical performances and EM force distributions has been done

### Technical challenges

#### ➤ Reliable operation




- Large-size irregular focusing mirror
- SMA (Steering Mechanism Assembly)
- Cooling, EM...

#### ➤ Irradiation resistance


- Material (mirror, Port-plug...)
- Shielding properties
- Interface with BSM

#### ➤ Remote handling


- Interface with RH
- The launcher suitable for RH maintenance



Quasi-optical unit




Shielding unit



Interfaces with RH, VV...

# 15. NNBI System of CRAFT Project



- Establish a **comprehensive research facility** for neutral beam injection system based on negative ion source.
- Developing negative ion source technology for NNBI and **cultivating a professional talent team**.
- Establishing a technical and talent foundation for **next generation** of fusion experimental device in china.


Parameters	Target Aim
Beam Species	H <sup>0</sup>
Beam Energy	200-400keV
Neutral Beam Power	2MW
Beam Duration Time	100s

**Comprehensive Research Facility for Neutral Beam Injection System Based on Negative Ion Source**


# 15. NNBI system

## Key technology



- Negative ions generation
- Negative beam acceleration
- HVPS and transmission
- High speed cryopump
- 400keV, 2-4MW, 1000s




Giant negative beam source




## CRAFT NNBI components




Neutralizer



Cryopump panels



Electrostatic residual ion dump



Calorimeter



# System Construction Status




**Comprehensive Testing Platform for Beam Source**



**Liquid Helium System @ 1kW**



**Control Center**



**Comprehensive Testing Platform for Beam Line**



**High Voltage Platform @ 400kVDC**



**High Voltage P.S. @ 200kVDC**




**Water-Cooling System**



# Latest Experimental Results

- Mastering key technologies for the generation and extraction of long pulse negative ions.
- Tackling key technologies such as high-voltage insulation, beam optics, and electron control.


The first round of **high-power** negative ion acceleration experiment



Dual driver negative ion beam source (single stage acceleration)




The first round of **high-energy** negative ion acceleration experiment



# 16. LHCD system

## Objectives

- Explore the feasibility of CFETR LHCD system.
- Developing all technologies needed for CW LHCD system.
- Building all components of LHCD.
- Integrated testing of 2MW system.
- RH compatibility testing of antenna with blanket.




Schematic diagram

## Key technology

- Developing 4.6GHz 500kW klystron
- The design and manufacturing of the near field coupling antenna.
- 500kW microwave components, oversized circular waveguide power transmission technology.
- The intelligent operation and control, to improve operating efficiency and to enhance reliability.

**Will be finished in the end of 2024**




System layout




Klystron  
 • 500 kW  
 • >1000 s



- The prototype of 4.6GHz 250kW/CW isolator has been designed and processed by Chinese manufacturer, passed **240kW/1000s** high power test **with matched load**, and **240kW/1000s** high power test **with 70kW reflected power**.




Electromagnetic simulation for 4.6GHz 250kW isolator




4.6GHz 250kW isolator on the test bench

- Current drive simulation and coupling characteristics analysis have been performed, inner structure of the antenna has been optimized. **Pre-research of key components has been completed.**




Reflection, Directivity Vs ne



Antenna front structure

Microwave simulation





Antenna system CAD model

# 17. ICRF System

To provide a testing facility with 2MW RF power for finding a solution to use ICRF in CFETR  
 Solving technical challenges and developing required technologies.  
 Manufacture, testing and validating of the key components for the CFETR ICRF system.



## CRAFT ICRF System

- **RF generator and power supply**
  - $2 \times 1.5\text{MW}$ , 40-80MHz, CW
  - HVPS with PSM and IGBT
- **3dB hybrid couplers**
  - $2 \times 1.5\text{MW}$  combination to 3MW
- **12 inch,  $50\Omega$ , coaxial transmission line**
- **Matching system**
- **Distribution antenna**
  - TWA antenna, 8 radiation straps




# CRAFT ICRF system



- **Transmitters:** Contract for 2 transmitters & HVPS, 2024 test.
- **R&D :** The prototype of DPA tetrode high power testing has achieved expected results ;The first FPA tube sample has been developed and achieved a test result of 1.2MW in 5 seconds, testing still on going.
- **Transmission line :** 12inch coaxial transmission line and elbow are preparing for testing.
- **R&D :** A quadrature hybrid coupler has been developed for combiner 2×1.5MW amplifier; combining testing with EAST high power transmitter, and successfully obtained 3MW combiner power.




DPA tube prototype testing , 100kW,1000s




FPA tube R&D, 1.5MW, 1000s



**RF windows:** RF design and thermal calculations finished; full scale ceramic cone ok



- **Antenna:** CFETR R F antenna optimization and conceptual design of the antenna structure on-going. A scale of 1/6 module of CFETR antenna is fabricated for testing



**Will be finished in the end of 2024**

# 18. Blanket testing facility

## 800 kW Electron Beam Gun

- Max. accelerating voltage: 60 kV
- Deflection angle:  $\pm 15^\circ$
- Frequency: 10 kHz
- Min. spot diam.: 30 mm

## 60 kW Electron Beam Gun


- Max. accelerating voltage: 120 kV
- Deflection angle:  $\pm 10^\circ$
- Frequency: 10 kHz
- Min. spot diam.: 1 mm

## Water loop

- Operating pressure: 15.5 MPa
- Inlet/outlet temp. of the test section: 285 °C/325 °C
- Max. high pressure flow rate: 25 m<sup>3</sup>/h
- Max. low pressure flow rate: 160 m<sup>3</sup>/h

## Vacuum chamber

- Inner diameter 3000 mm
- Length 4000 mm
- Vacuum: 10e-3 Pa







Electron Beam Guns

Vacuum chamber

Water loop

# High temperature PbLi loop



Ultrasonic Doppler Velocimeter

## Main parameters

Operating pressure	1.5 MPa
Design temperature	High temp. section (310s) 750 °C Low temp. section (316L) 550 °C
PbLi operation temperature	270-700 °C
PbLi flow rate	30 m <sup>3</sup> /h
PbLi inventory	10 t
Magnetic field	0~3 T, uniformity of 8% in 0.25 m×0.6 m×1.0 m region
Oil design parameter	1.6 MPa, 350 °C, 130 m <sup>3</sup> /h
Water design parameter	0.5 MPa, 80 °C
Heating power	1.5 MW

## ◆ Turbulent heat transfer experiments

- Thermal boundary layer flow on forced convection
- PbLi flow in complex geometry channel

## ◆ MHD effects experiments

- Phase diagram and turbulent transition mechanism under different Re/Ha
- The effects of FCI on the flow and heat transfer
- MHD flow in complex geometry channel
- Multi channel under electromagnetic coupling effect

## ◆ Mixed convection experiments

- One-side heat flux conditions
- Large magnetic/heat source



# 19. RH Testing Facility


The blanket remote handling system is developed to install/remove all the 5 blanket segments beneath of each vertical port. The blanket segment is **60t in weight and 7 meters in height**.



Three winches work together to lift the Blanket. The lifting cask frame and crane system were **successfully delivered in April 2023**.




Blanket toroidal Mover system, **repositioning accuracy  $\pm 1$  mm**. Two mover system finish the factory acceptance test in **June 2023**.



Blanket Transport Manipulator with 7 degree of freedoms (under joint developing with EUROfusion)

Double door test bench for opening/closing mechanism and leak tightness verification ( $2.5 \times 10^{-3} h^{-1}$ ). This test bench will be manufactured in 2023.8.



**Cooperation with EU-DEMO RH group**


# 19. RH Testing Facility

## ➤ Key technology


- High reliability, heavy load maintenance mechanism
- Maintenance tools (cutting, welding, bolting ...) and end-effectors (dual-arm, snake-arm ...)
- Remote handling compatibility design
- Remote control technology




**Flexible dual arm**  
**Payload: 25 kg**  
**Repeatability: ± 1 mm**




**Divertor RH**  
**Payload: 15 t**  
**Position accuracy: ± 10 mm**



**Blanket RH**  
**Payload: 60 t**  
**Position accuracy: ± 20 mm**



**Heavy-duty manipulator**  
**Payload: 2.5 t**  
**Repeatability: ± 10 mm**




**RH Tools: cutting, welding, bolting**



# Remote Handling System

CMOR(CFETR Multipurpose Overload Robot), used for maintenance the first wall componentse, is one of the most powerful motor driven robot with **10 meters long and 2.5 tones capacity**.




CMOR in VV mockup

**CHENG's talk on 21th**



- Joint prototype and testbed have been manufactured and qualified
- Full scale robot is under construction, will be completed in June 2024



- Dexterous manipulator being assembled
- 30kg per arm, 100kg for crane



- Qualified in-bore cutting tool for divertor
- $\varnothing 51\text{mm}$  with 3mm thickness








# 20 VV and installing testing facility

## ➤ Manufacturing completion


- ✓ Based on precision measurement and reverse engineering,  
Assembly accuracy  $\leq 1\text{mm}$
- ✓ In-site weld length :  $\sim 190\text{m}$
- ✓ Groove type: 50mm full penetration
- ✓ Welding quality: ISO-5817 level B
- ✓ Surface deviation  $\leq \pm 8\text{mm}$



iGPS dynamic measurement



Measurement controlling network






finished on May of 2023



# VV and installing testing facility

## ➤ Completion of automation system

- In-site automatic machining system, NG-TIG welding system, automatic PAUT system have been built and applied in the assembly process of sectors.



In-site machining system

In-site automatic PAUT system

# Campus and Buildings

- B1-4** Office & guest house
- B5** 110kV substation
- B6** Cooling water
- B7** Power supply
- B8** Superconducting
- B9** Cryogenic
- B10** H&CD
- B11** Vacuum vessel +remote handling
- B12-13** Divertor, blanket test facility
- B14** Exhibition room & general control hall





# Campus of CRAFT



# Summary

- CRAFT is a national big science facility aiming to develop key technologies and systems for CFETR.
- The construction of CRAFT started on Sept. 20, 2019 which should be finished within 5 year and 10 month with joint founds from central and local governments.
- CRAFT will use not only the technologies from ITER, but also those which need to be developed in future with significant challenges and efforts.
- CRAFT will provide a solid technical base for successful construction of CFETR in future. **Completeness is 79%.** It is within budget and about **8 month delay.**
- CRAFT will fully open to world fusion community, joining construction and future integrating experiments are welcomed.



**Thanks!**

