

EUROfusion


ENR-TEC.02.CEA WEST ICRH TWA Project 2024 Activities

8th SB.ENR-TEC

Monitoring of 2024 activities

05/02/2025

J.Hillairet for the WEST TWA team





■ Introduction

Current Ion Cyclotron Antennas have Several Drawbacks

While ICRF has been proven to be a relevant tool in fusion experiments due to

- No density limit (high-density plasmas)
- Excellent absorption
- Proven experience in relevant scenarios (heating, wall-conditioning, breakdown)
- Proven technology for CW and modest price/MW (compatible with high field experiments)

Current ICRF Antennas suffer from drawbacks making them incompatible with fusion plants

- Low coupling conditions (Large antenna to fast-wave cut-off distance)
- Undesirable Large Voltages and Currents inside the antennas (Arcs)
- Metallic Impurity production (RF Sheaths)
- Low Reliability, Availability, Maintainability and Inspectability (RAMI)
- Large antenna volume and weight (Tritium breeding requirements)

Traveling Wave Array (TWA) Antennas for ICRF

An innovative antenna concept for the ICRF




- Array of tuned straps
- RF Current is induced by mutual coupling between elements
- No direct feeding of each element
- “Slow-wave” RF structure (exciting plasma fast-wave)
- Power *leaks* to the plasma

High-power mockup successfully tested in 2021 in Vacuum

- 2 MW / 3 s (limited by RF generator only) and 1.75MW/5s
- 500 kW / 60 s
- No pressure increase during long pulses
- Thermal & Electrical responses as expected by modelling

[Chiu 1984 [Nucl. Fus.](#) 24]
[Moeller 1994 [AIP Conf. Proc](#) 289]
[Ragona 2016 [Nucl. Fus.](#) 56]

[Ragona 2022 [Nucl. Fus.](#) 62]




Motivations: Demonstration of ICRF TWA antenna in WEST

Advantages of operating a TWA antenna in a W-environment

- Provides mechanical simplicity (no tuning elements in vacuum)
- Increased RF coupling ($k_{//}$ spectrum narrower and of lower value)
- Fusion power plant compatibility:
 - Materials, reliability, efficiency
- Lower Electric Field
 - Reduced risk of Arcs and Impurity Production during long pulse operation
- Enhanced directivity
 - Reduced Parasitic Coaxial Mode Excitation (reduced impurity)
- If possible: assess the requirements of a Faraday Screen
 - Comparing one TWA with and one without Faraday Screen
- Large bandwidth: allows to change the RF frequency (power deposition) in real-time
 - New operational scenarios!

Objectives of the TWA Antennas Project

- Two poloidal rows
 - Current preferred implantation in port Q4A
 - Replacing Q4 antenna
- CW Antenna
- Same plasma scenarios than currently
- RF power scenarios goals (2 rows):
 - Limits on max power & durations takes into account plant/lines/feedthroughs
 - 4 MW peak coupled power (duration *tbd*)
 - 3 MW coupled power 30 s
 - 1 MW coupled power/1000 s
 - ICWC to be investigated
- Material: bare Stainless-Steel
 - No coating (fusion plant relevance)
- Faraday Screen
 - One antenna without
 - One antenna with if possible
- Eventually integrated inside the wall/blanket (WEST Phase 3)





■ ENR Activities

ENR-TEC.02.CEA 2024 Activities

■ Project Started: May 2024



■ Scenario Development

- EVE and TOMCAT ICRH scenarios
 - 57 +/- 5 MHz bandwidth
 - Parallel wavenumber between 8 and 10 rad/m
 - (Avoid damping too much on electrons)

■ WEST ICRH TWA system System Specifications

- Actively cooled launchers
 - 3 MW/30s and 1 MW/1000s (2 rows)
 - From one equatorial port of WEST
- ## ■ RF Design mostly achieved
- ## ■ Load Specifications
- Plasma and RF thermal fluxes
 - Structural and electromechanical loads
- ## ■ Mechanical design started



Case 4 - SPA fractions



WEST Travelling Wave Array system Conceptual Design Review Passed

11th & 12th of December 2024


- Review of the current design of the WEST TWA by an international panel
- Main points (“Chits”) to address for the future Preliminary Design Review (PDR) mid-2025:
 - Faraday Screen feasibility
 - Assess launchers radial position
 - Finalize the antenna boxes and inner connections
 - Consolidate the in-vessel assembly sequence



Project Current Status (2025-01)

- Antenna RF design mostly completed (ERM + DTU)
- Mechanical design on-going (IRFM/GCIF)
 - Conceptual mechanical modelling (structural, EM, thermal) done or on-going
- CDR 11&12/12/2024 Passed
 - No showstoppers have been identified by the CDR review panel.
- The work will continue towards a Preliminary Design Review by the middle of 2025
- No modifications to the project for 2025 for the moment





Questions?

Julien Hillairet
CEA/IRFM