



EUROfusion General Programme Meeting Nov 4th, 2025

ASDEX Upgrade: machine news and programm for 2026(127)




Thomas Pütterich on behalf of the ASDEX Upgrade team

AUG finished 1st Campaign with new upper divertor (ADCs!)




Final in-vessel panorama view
August 2024


Upper divertor upgrade






Upper divertor upgrade



Upper divertor upgrade



Flat tile target in the upper divertor fulfills tolerances




Strict tolerance requirements to avoid leading edges


- alignment of most exposed tiles by excentric bolts on the lower side
- height offsets below $300\text{ }\mu\text{m}$ were met

No leading edges detected for both field helicities

#41980, $B_{\text{tor}} = +2.5$




#41982, $B_{\text{tor}} = -2.5$



Both helicities with 4.5 MW ECRH heating, symmetric flat divertor tiles with no tilting

All Alternative Divertor Configurations (ADC) achieved!


- All envisaged configurations
- Up to ~20 MW of heating
(world record in ADC, P/R~12)
- $I_p = 0.6\text{-}1.0\text{MA}$
- Seeding of N, Ar, Kr
- Detachment



Very good Diagnostic Coverage in new Upper Divertor

Example: electron temperature

- Quantitative agreement in low density L-mode plasma between:
 - Langmuir probes
 - Thomson scattering
 - Gas puff imaging (GPI)
- Spectroscopy** can replace GPI at higher densities
- Detailed comparison is **ongoing work**







Issues identified during/after the campaign

- The cryo pump did release pumped gases during plasma operation (Clear evidence for Ne and D), He pumping seems less efficient – why?
 - ⇒ plasma radiation, ECRH stray field, role of arcs (?)
- Strong disruptions led to a damage of the lower divertor tile
- Vacuum flanges below divertor structure loosened during operation
- Arcing at the cryo-pump pipes observed


Hardening of the Cryopump against radiation

Installation of plates closing the gap between CP housing and chevron to reduce the both plasma radiation and ECRH radiation (plates coated with TiO-AlO)

Installation of the coated absorption plates in the inner divertor



Leak on the lower divertor: repair the leak!



Issues identified during/after the campaign





- The cryo pump did release pumped gases during plasma operation (Clear evidence for Ne and D), He pumping seems less efficient – why?
 - ⇒ plasma radiation, ECRH stray field, role of arcs (?)
- Strong disruptions led to a damage of the lower divertor tile
- Vacuum flanges below divertor structure loosened during operation
- Arcing at the cryo-pump pipes observed

⇒ Repair and Improvement Actions made the vent longer

- Cryo hardening and tightening againsts plasma and ECRH radiation
- Cryo hardening against arcing
- Repairs of tiles and additional isolation of current paths through tiles
- Removing of lower divertor structures necessary to repair flanges (makes vent much longer)


NBI upgrades (new in 2024)

- NBI box I switched from arc to RF sources
- NBI box II all sources with variable gap (as source 5 in 2022)
- Fully commissioned



- New upper divertor diagnostics fully operational including divertor Thomson scattering
- Upper GPI diagnostic at low densities (PhD thesis ongoing)
- Dispersion interferometer and MANTIS available (PhD theses going on)
- Will the cryo-pump performance improve?
- Outer midplane diags show issues for USN due to high neutral/plasma interference (under inv.)
- ECRH: 7 gyrotrons (one gyrotron retired, still 4.5-5MW), end of 2027 again 8 gyrotrons => 5.5-6MW
- ICRH: 2026 no change, 2027: new generator enables 6MW total power + additionally 24MHz @ <2MW
- $B_t=3.5T$ possible with short flat-top time (max flat-top in $B_t \sim 3s$), commissioning in plasma pulse necessary
- **Possible machine safety measures discussed**
 - **Fast ion loads on outer limiters**
 - **Disruption forces**

ASDEX Upgrade Schedule 2026/27



1st boronization on 13th of april, restart from 14.4. (maybe earlier ?)

2nd boronization on 27.04. Proposal execution from 28.04. (maybe earlier?)

WPTE Campaign 2026/27:

28th of Apr 2026 to Jul 2026 + Nov/Dez 2027 + Jan 2027 to Jul 2027 + Nov/Dec 2027

At current planning: 622 discharges