



# JET timeline update and future post mortem analysis opportunities

**Anna Widdowson**

**JET**



This work has been carried out within the framework of the EUROfusion Consortium and has received funding from the Euratom research and training programme 2014-2018 and 2019-2020 under grant agreement No 633053. The views and opinions expressed herein do not necessarily reflect those of the European Commission.




- Update on JET timeline
- Implications for availability of new samples from JET post DTE
- Review and retention of available materials from JET

# Shown at 2019 annual meeting....




**JET24** - Proposal for extension of JET to 2024 supported by UK government to deliver upgrades and enhancements.  
**BUT** where are we now...?



# Current JET timeline to end 2021



JET 2020-2021 Schedule<sup>1</sup>



<sup>1</sup>presented at the EUROfusion General Assembly 6-7 July 2020


- Proposals for JET experiments to end of DTE2
- No enhancements
- No in-vessel activities (i.e., no sample removal)
- Move to decommissioning in 2022

# Revised JET extended timeline to 2024

- Proposal supported by UK government
- Endorsement from EUROfusion at GA in July 2020 – NOT agreed
- Reduced scope to JET24 upgrades & enhancements
- No in-vessel activities planned during operations
- Potential removal of samples after operations relies on significant remote handling upgrade



Programme elements ~fixed



# Changes to JET24 planned upgrades

Discussion with EUROfusion/proposed at GA – **NOT**  
agreed

**red - cannot proceed orange – reduced scope**

No in-vessel activities before end of operations

## 1. SPI2 enhancements

- SPI2
- SPI2 Knock on
- SPI2 Support - Bolometry
- SPI2 Support – Cameras

## 2. LIBS/LIDS enhancements

- LID-QMS delivering LIDS capability to JET
- LIBS/LIDS Phase 2 - Heated Tiles
- LIBS/LIDS Phase 3 - Deployment by RH

## 3. AGHS refurbishment

- AGHS update for N compatibility

## 4. RHSME refurbishment

- Remote Handling System upgrade


## 5. Integrated Upgrades for refurbishment....

- Asset Management
- Building and infrastructure
- CODAS
- Cooling systems
- Diagnostics (following DTE2)
- ICRH systems
- NBI systems
- 36kV distribution
- Tokamak power supplies
- Vacuum systems

## .... and diagnostics enhancements

- ITER mirrors
- Black Calibration Tile
- SXR with thinner filters (now software)
- Divertor pressure gauges
- Divertor spectroscopy upgrades

# UK government and UKAEA look to commit funds to reintroduce SPI2



- UK recognise the importance of SPI2 as expressed by ITER STAC
- UK are prepared to proceed at risk on everything controlled at UKAEA to keep open the option of a shutdown and enhancements including SPI2
- This would move JET24 back to something like the original schedule, but with a ≈ 5 month shift in DTE2 and the following timeline

NOTE: Shown timeline is illustrative of proposed operations – exact dates have shifted + 6 months. Operations would still end at end of 20204.

# Changes to the planned upgrades

## Early discussions with Eurofusion - **NOT** agreed

### 1. SPI2 enhancements

- SPI2
- SPI2 Knock on
- SPI2 Support - Bolometry
- SPI2 Support – Cameras

**Looking to reintroduce**

### 2. LIBS/LIDS enhancements

- LID-QMS delivering LIDS capability to JET
- ~~LIBS/LIDS Phase 2 - Heated Tiles~~
- LIBS/LIDS Phase 3 - Deployment by RH

### 3. AGHS refurbishment

- AGHS update for N compatibility

### 4. RHSME refurbishment

- Remote Handling System upgrade

### 5. Integrated Upgrades for refurbishment....

- Asset Management
- Building and infrastructure
- CODAS
- Cooling systems
- Diagnostics (following DTE2)
- ICRH systems
- NBI systems
- 36kV distribution – **Looking to reintroduce**
- Tokamak power supplies
- Vacuum systems

### .... and diagnostics enhancements

- ~~ITER mirrors~~
- ~~Black Calibration Tile~~
- SXR with thinner filters (now software)
- ~~Divertor pressure gauges~~
- ~~Divertor spectroscopy upgrades~~





- **JET 2020 timeline does not include sample recovery**
- **Extended JET 2024 programme will not include in-vessel access**
- **Sample removal may only occur after JET operations completed**
  - Availability of remote handling
    - Significant upgrade foreseen in JET24 programme
    - Also needed for LIBS – deployment by remote handling
  - Capability for handling, preparing and analysing activated, tritiated, beryllium containing samples at laboratories
  - Cost analysis of retrieval and scientific output



## Removal of tiles would depend on availability of spares (new or used) or firm decision on end of life

- HFGC used as LID-QMS target & HFGC for comparison – validation
- Tile used for LIBS deployed by remote handling (future JET24 project) – validation

## Diagnostics installed in 2017: VOLUNTARY (VR, CCFE, IPP, FZJ)

### Outer wall:

- Mo irradiated mirrors – Fuel retention in damaged surfaces
- Rotating collector – time resolved deposition in DT
- Dust collectors – Dust & deposition

### Inner wall:

- Inner wall cladding inserts W:Be - Erosion and retention in DT operations
- W Sticking monitors – Deposition/sticking on W surface, dust
- Dust collectors – Dust & deposition


### Inner & outer divertor: Migration and retention in remote areas in DT

- Mirror-like deposition monitors (steel) - splashes & dust
- QMB covers - deposition monitors, splashes & dust
- Rotating collectors – time resolved deposition in DT

# Erosion/deposition diagnostics: Outer wall & divertor




Oct 8      Oct 7      Oct 6      Oct 5      Oct 4      Oct 3      Oct 2      Oct 1



- Mirrors - (divertor deposition monitors, outer wall damaged/non-damaged)
- Rotating collectors
- QMB 5 (cover = deposition monitors)
- Dust collectors

Rendered image – NOT photograph

# Erosion/deposition diagnostics: Inner wall & divertor



- 1Z 2X 2Z 3X 3Z 4X 4Z 5X 5Z 6X 6Z 7X 7Z 8X 8Z 1X
- Mirrors (deposition monitors)
  - Rotating collector
  - QMB 1, 2, 3, 4 (covers = deposition monitors)
  - Inner wall cladding inserts 50:50 W:Be
  - Tungsten sticking monitors
  - Dust collectors
  - HFGC tile – target for LID-QMS

Rendered image – NOT photograph


# Sticking monitors – inner wall



OCT3




OCT5




# Sticking monitor and mirrors: Tile 5



Photograph showing location of W-sticking monitor on 14W tile 5  
Photograph from 2014 installation





Photograph showing location mirrors  
14N tile 5 installed in 2017



Mirrors 308, 310  
Mirrors 311, 312

W sticking monitor

# IWC insert & inner wall dust collector





## **Return of samples and tiles is extended to end March 2021**

- Research institutes may elect to keep samples, but need to demonstrate disposal route
- Don't delay – please send samples now in no longer needed

## **Review of all tiles, samples and diagnostics for retention at CCFE underway**

- Any item not designated for retention will go in to waste stream and will no longer be available for analysis
- Whole tiles (W-CFC, W, Be, Be-Inconel) to be kept as potential “hot/used” spares for JET
- Selection of W-CFC cores and partially cored tiles cut at VTT have been selected for retention – complete JET-ILW divertor cross section, few MkIIa
- Be castellation samples and tile pieces (except marker coated) to be retained
- W lamellae samples (except marker coated) to be retained
- Mirror samples
- Langmuir probes (tungsten) removed in 2014 after damage – melting & cracking
- Remaining diagnostics to be reviewed



## **Be castellation samples from tiles in-vessel ILW1-3**

- WPL 4D15 and IWGL 2XR11
- Samples at CCFE and will be shipped in November 2020 [Be-D-65]
- Research units to receive samples: IAP, VR, FZJ, VTT, UoL, CCFE
- Delayed deliverables to 2021 Be-D-66, Be-D-67, Be-D-68, DG-01, DG-03, DG-04, DG-05

## **Cores from HFGC in-vessel ILW1-3**

- Final few TDS measurements [WC-D-49] and SEM surface/dust characterisation [WC-D-48]

## **Sample of beryllium filter in JET exhaust ventilation system**

- Continued delay at CCF due to resource and access to BeHF (coronavirus)
- Sample due to be sent to IPPLM for SEM/EDX
- Delayed deliverable to 2021 D-RH-04

## **Langmuir probe – non-exposed**

- Sample due to be sent from CCFE to IPPLM for nanoindentation – delayed (coronavirus)
- Comparison with data from exposed sample
- Delayed deliverable to 2021 MT-03